



Construction to Maintenance Handoff December 5th, 2019



Center for Environmental Excellence

- Promotes environmental stewardship and encourages innovative ways to streamline the transportation project delivery process.
- Provides technical assistance, training, information exchange, partnership-building opportunities, and quick and easy access to environmental tools.
- Provides a variety of products and services to assist transportation agencies in achieving environmental excellence including:
 - Peer Exchanges
 - Practitioner's Handbooks
 - Communities of Practices
 - Webinars
 - Databases

https://environment.transportation.org



AASHTO and FHWA



Melissa Savage

AASHTO Center for Environmental Excellence



Oscar Bermudez

AASHTO Center for Environmental Excellence



Susan Jones, PE

Federal Highway Administration



Community of Practice Presenters



Pete Riegelhuth

California Department of Transportation



Heather Voisin

Vermont Department of Transportation



Jennifer Callahan

Vermont Department of Transportation



Scott McGowen (Moderator)

Michael Backer International




Community of Practice Forum Overview

- I. 90% Walkthrough Construction to Maintenance Handoff
 - Pete Riegelhuth, California Department of Transportation
- II. The Flow of Stormwater on Vtrans Projects An Evolving Process
 - Jennifer Callahan, Vermont Department of Transportation
 - Heather Voisin, Vermont Department of Transportation
- III. Community of Practice Forum
 - Scott McGowen, Michael Baker International
- IV. Closing



90% Walkthrough Construction to Maintenance Handoff



Pete Riegelhuth

D-5 NPDES Coordinator

California Department of Transportation






90%Walkthrough Construction to Maintenance Handoff

So the state

Presentation by: Pete Riegelhuth

Construction Policy Bulletin 13-1

- Effective July 27, 2013
- Due to projects ending with... "elements such as structural treatment best management practices (BMPs), drainage systems, and permanent erosion and sediment controls that were not functional or maintainable."







Maintenance Reviews Sec 5-006

 Requires a project field review with Maintenance at approximately 90% completion.

 To identify items necessary to comply with the NPDES Permit and the Construction General Permit



Final Inspection and Contract Acceptance Sec 3-523

 Resident Engineer schedules a final inspection review with Maintenance and other Caltrans divisions.



 During the 90 percent field review meeting, the resident engineer and district maintenance stormwater coordinator will complete Form MTCE-0023, "Construction to Maintenance 90% BMP Completion Walkthrough."



STATE OF CALIFORNIA • DEPARTMENT OF TRANSPORTATION CONSTRUCTION TO MAINTENANCE 90% BMP COMPLETION WALKTHROUGH MTCE-0023 (REV 10/2018)

Project ID Number EA Number		Inspection Attendees					
Date							
Project Information (S	statement of Ongoing Contract of Contract	ontracts http://www.dot.ca.gov/hq/construc/state	ement.html)				
Project Limits Co - Route - PM1 to PM2		Estimated Completion Date	Estimated Acceptance Date	EFIS Unit	District Cost Center		

1. List the New, Removed, and Modified Treatment BMPs Within the Project Limits. If none, select "NONE" in the TBMP Type field and delete the remaining rows. (Note: Final approval includes receipt of an O&M manual if applicable)

#	TBMP Type	Count	/ Route	Direction of Travel	Begin PM	Begin Latitude	End Latitude	CCO	State Any Corrective Actions Needed on the Treatment BMP
"	тымп туре	County	Route	Direction of mayer	End PM	Begin Longitude	End Longitude	Filed?	State Any conective Actions Needed on the Treatment Divi
±,								YES	×
1								NO NO	
±_] [YES	X
2			1 L					NO NO	
±								YES	X
2			1 L					NO NO	
±,] [YES	X
4			1 L					NO NO	
±_								YES	X
5			1 1					NO NO	

2. Drainage System. ONLY identify locations where additional work is needed prior to acceptance. If none is needed enter "NONE" in the Additional work needed field and delete the remaining rows.

#	County	Route	Direction of Travel	Postmile	Latitude	Longitude	Additional work needed prior to acceptance
± 1	-	•	•				×
±2	•	•	•				X
±3	-	•	•				X
± 4	-	•	•				×
± 5	-	•	•				



Walkthrough Topics

- Post Construction Runoff Control TBMPs
- Drainage System
- Illegal Connection/Illicit Discharge IC/ID
- Temporary Construction Site BMPs
- Permanent Erosion Control (Slope Stability)
- Plant Establishment
- Offsite Contractor Facility Cleanup



Where is the Bioswale?





How about this bioswale?





Current Day





Current Day





Identify Deficiencies





Go over maintenance requirements with field staff.



Caltrans Stormwater Quality Handbook Maintenance Staff Guide

CTSW-RT-18-314.20.1 May 2018

California Department of Transportation Division of Environmental Analysis, Stormwater Program 1120 N Street Sacramento, California 95814 http://www.dot.ca.gov/hq/env/stormwater/



Maintenance Indicator	Inspection Frequency	Maintenance Activity			
Evidence of significant channeling, erosion, seeps, or ponding	Annually in late wet season	Correct channelized, eroded, seeped, or ponded areas using additional fill and vegetation depending on coverage and/or by removing accumulated sediment.			
		Complete prior to next wet season.			
Average vegetation height exceeds 12 inches, emergence of trees, or woody vegetation	Semi-Annually, once during wet season, once during dry season (depending on growth)	Cut vegetation to a minimum height of 6 inches; cuttings may be removed at discretion of District Maintenance.			
Less than 70 percent background coverage in swale invert and swale side slope	Semi-Annually, once late wet season and once late dry season	Assess quantity needed and reseed/revegetate barren spots by November. Contact environmental or landscape architect for appropriate seed mix. Scarify area to be restored, to a depth of 2- inches. Restore side slope coverage with hydroseed mixture. If growth is unsuccessful after 2 applications (2 seasons) of reseeding/revegetating, consult with District Landscape Architect for potential solutions. Maintain shrubs and trees that were installed in the original design			
Debris/trash present	Inspect during routine trash collection. Minimum twice per year during inspections.	Remove litter, and debris per routine District schedule.			
Sediment at or near vegetation height, channeling of flow within swale and energy dissipaters, inhibited flow due to change in slope	Annually in the dry season	 Remove sediment. If flow is channeled, determine cause and take corrective action. If sediment becomes deep enough to change the flow gradient, remove sediment during dry season, characterize and properly dispose of sediment, and revegetate. Refer to Activity Cut-Sheet Page B- 72. Notify engineer or District Maintenance Storm Water Coordinator to determine if regrading is necessary. 			
		 If regrading is necessary, regrade to design specification and revegetate swale /strin_Regrading should start in May_Revegetate strin/swale by 			



Common Issues

- Infiltration Areas-Vegetated or non-vegetated and Compaction
- Bio-swales/strips use vegetation and infiltration to remove pollutants from runoff. (70% Vegetative Cover Requirement)
- Maintaining the vegetation in the bio-strip/swale is the key to success.
- It is important to maintain the bio-strips/swales as originally designed. (width & side slopes)
- Walk staff through the parts of Detention/Infiltration Basins.
- Trash



Pesticide Use- No No No





Vegetation Control

- DO NOT use herbicide to kill the grasses.
- DO NOT use court referral labor to remove the grasses.
- It's okay if the grass looks dead. Leave it as is.

Per Maintenance Staff Guide



San Luis Obispo- NB-101 Shoulder





San Luis Obispo- NB-101 LOVR to Prado Road





San Luis Obispo- NB-101 LOVR to Prado Road



Caltrans





Temporary Construction Site BMPs





Temporary Construction Site BMPs





Learn from mistakes- Mulch vs...





Native grass sod












Detention Basin- Hwy 46



Talk about how they work- the parts



Maintain the Orifice






Maintain the Orifice





Maintain the Orifice





Look at Slope Stabilization





Look for scour problems





Look for conflicts





Access Points






Do they drain properly









Finalize TBMP Inventory






Provide list and calcs- As Builts

TREATMENT TYPE AND LOCATIONS

	Treatment		Direction of							Tributary	BMP Size		Length	Width	Begin	
No.	BMP	County Ro	oute Travel	Begin PM	Begin Lat	Begin Long	Ending PM	Ending Lat	Ending Long	Area (sqft)	(sqft)	wqv	ft	ft	Station	End Station
	DPP Infiltration															
	BMP-1	MON	101 SB	87.520	36.680874	-121.642465	87.740	36.68312	-121.645143	44,308.00	17,519	1,08	6 1,200)	10 264+50	276+50
	DPP Infiltration		101 00 11 11	00.470			00 450		101 000710						10.015.00	252.52
	BMP-2	MON	101 SB Median	88.470	36.688833	-121.655709	89.150	36.69613	-121.663712	164,484.00	53,584	4,03	0 3,550)	10 315+00	350+50
	DPP Infiltration BMP-3	MON	101 NB Median	00 470	26 600022	-121.655709	00 070	26 60271	-121.662135	106.208.00	16,678	2,60	2 2,600		10 315+00	341+00
	DPP Infiltration	WON	101 NB Weulan	00.470	50.000055	-121.055709	66.970	50.09571	-121.002135	100,208.00	10,078	2,00	2 2,000	,	10 313+00	541+00
	BMP-4	MON	101 SB Off	89.394	36.69923	-121.66608	89 450	36 70001	-121.66609	9,440.00	5,829	23	1 400		10 372+00	376+00
	DPP Infiltration		101 30 011	05.554	50.05525	121.00000	05.450	50.70001	121.00005	5,440.00	5,625	20	400	·	10 572.00	570.00
	BMP-5	MON	101 SB Median	89.350	36.698937	121.665019	89.580	36,7021	-121.666281	51,990.00	18,204	1,27	4 1,200)	10 361+50	373+50
	DPP Infiltration									,		-,				
	BMP-6	MON	101 NB Shoulder	89.480	36.700691	-121.65827	89.580	36.70945	-121.664087	188,141.00	72,179	4,61	0 4,754	4	10 367+96	415.5
	DPP Infiltration															
	BMP-7	MON	101 SB Median	89.600	36.702395	-121.666329	89.760	36.70473	-121.666189	31,660.00	9,537	77	6 850)	10 374+50	383+00
	DPP Infiltration															
	BMP-8	MON	101 SB Shoulder	89.840	36.705833	-121.665767	90.964	36.72175	-121.66143	230,195.00	89,099	5,64	0 3,000)	10 387+00	417+00
	DPP Infiltration													_		
	BMP-9	MON	101 NB Shoulder	90.780	36.718721	-121.660721	90.910	36.72058	-121.660228	25,185.00	9,779	61	7 650)	10 443+50	437+00
	DPP Infiltration BMP-10	MON	101 CD Chaulder	00.910	26 71015	121 000721	00.010	26 72059	121 660228	20 647 00	7 5 2 5	50	6 500		10 429-50	443+50
	DPP Infiltration	MON	101 SB Shoulder	90.810	30./1915	-121.660721	90.910	30.72058	-121.660228	20,647.00	7,525	50	0 500	,	10 438+50	443+50
	BMP-11	MON	101 NB Off	90.891	36.72016	-121.65967	90 947	36.72984	-121.65901	13,497.00	5,310	33	1 350		10 442+50	446+00
	DPP Infiltration	MON	NB On Loop	50.051	50.72010	-121.05507	50.547	30.72504	121.05501	13,437.00	5,510		1 350	·	10 442150	40.00
	BMP-12	MON	101 Ramp	90.969	36.72164	-121.65893	90.999	36.72136	-121.65964	17,792.00	7,272	43	6 600)	10 440+00	446+00
	DPP Infiltration										.,			-		
	BMP-13	MON	101 NB On Shoulder	91.058	36.72239	-121.65836	91.130	36.72391	-121.65878	7,380.00	4642	18	0 328	3	10 449+00	452+28
	DPP Infiltration															
	BMP-14	MON	101 SB Shoulder	91.060	36.722724	-121.659656	91.080	36.72301	-121.659578	4,185.00	1,505	10	3 100)	10 431+50	432+50
	DPP Infiltration															
	BMP-15	MON	101 NB On Shoulder	91.169	36.72426	-121.65879	91.226	36.72505	-121.65867	6,992.00	4415	17	1 300)	10 454+00	457+00
	DPP Infiltration															
	BMP-16	MON	101 SB Off Shoulder	91.152	36.72435	-121.66026	91.255	36.72589	-121.65924	13,911.00	8825	34	1 600)	10 471+00	477+00
	DPP Infiltration												_	_		
	BMP-17	MON	101 SB Shoulder	91.170	36.724297	-121.659229	91.210	36.72487	-121.659073	9,666.00	3000	23	7 200	0	10 457+50	459+50
	DPP Infiltration	MON	101 ND Chaulder	01 270	26 725 720	101 65004	01.400	26 72074	101 050004	62 512 00	0535	1.00	c 1454		10 462-50	474.00
	BMP-18 DPP Infiltration	MON	101 NB Shoulder	91.270	30.725728	-121.65884	91.480	56./28/1	-121.658034	63,513.00	9535	1,55	6 1150	,	10 462+50	474+00
	BMP-19	MON	101 SB Shoulder	01 290	36 725 871	-121.658801	01 /00	36 72871	-121.658034	53,145.00	15980	1,30	2 1,060		10 463+40	474+00
	DIVIP-19	WON	TOT 3D SHOULDEL	91.280	30.7256/1	-121.056801	91.480	30.726/1	-121.056034	55,145.00	12980	1,30	2 1,000	,	10 405+40	4/4+00




Maintenance needs mapping





They need the details






Structural TBMP-STBMP Form

IMMS

	LIFORNIA - DEPARTN			DACE		,		
	ATA ENTRY FOR	KM	•	PAGE	1	of		
IMMS Appurton	anco Numbor Roquost							
	Uso this form when request See	ing a now Structural a d campleted far				•numborfram	IMMS.	
REQUESTER INFOR	MATION							
REQUESTED	BT:	PHONE NUMB	ER I	DATE REG	QUESTED	EMTERED	INTO IMMS	5 BT:
]						
STRMP INFORMATI	юн							
DISTRICT	COUNTT	ROUTE	"POST HIL	LE	DIRECTI	ON OF TRAY	FEL	
TTPE (SEE DES	RIPTIONS DELOW	ASSIGNED CO	ST CENTER		LOCATIO	N (RHS, CI), Romp Et	c.)
FIELD TERIF	IED? (T/H)							
DESCRIPTIT	ELOCATION (Any other	_ rinformation not incl	udad abava)					
IKAL STOMP :-	Incated in a Maintenance S				-			
		station, enter the par	emile neareseer	ne racility.	312 41414 1			,
Le this STBMP in	Caltranz Facility? WN							
Additional Information								
	R COORDINATOR	LENGTH	WIDTH I	нібнт	DATE INS	TALLED		
STORMWATE	R COORDINATOR							
STORMWATE		LENGTH DATE SENT				TALLED	łY	
STORMWATE	R COORDINATOR						RΥ.	
STORMWATE	R COORDINATOR						łY	
STORMWATE	R COORDINATOR						łY	
STORMWATE	R COORDINATOR						łY	
STORMWATE	R COORDINATOR						łY	
STORMWATE	R COORDINATOR						γ	
STORMWATE ASST. SW Co COMMENTS:	ER COORDINATOR						γ	
STORMWATE	ER COORDINATOR						۶Y	
STORMWATE ASST. SW C4 COMMENTS:	ER COORDINATOR	DATE SENT					<u></u> γ	
STORHWATE ASST. SW GO CONHENTS: IMMS Tredeval Pro	ER COORDINATOR DORDINATOR 	DATE SENT					₹¥	
STORHWATE ASST. SW CO CONHENTS: IMMS CODE BIOSTP	ER COORDINATOR DORDINATOR DORDINATOR DORDINATOR DESCRIPTION BIOFILTRATION-BIO	STRIP -SWALE					₹Y	
STORHWATE ASST. SW GO CONHEETS: IMMS CODE BIOSTP BIOSTP BIOSTP BIOSTP CNTBOX CNTBOX	ER COORDINATOR DORDINATOR DORDINATOR DORDINATOR DESCRIPTION BIOFILTRATION-BIO BIOFILTRATION-BIO BIOFILTRATION-BIO GSRD - CONDERTE I CONT. DEFLECTION	-STRIP -SWALE BOX INCLINED SC					37	
STORHWATE ASST. SW C4 C+HHETTS: IMMS CODE BIOSTP BIOSTP BIOSTP BIOSVL CHTBOX CHTDEFF DETBAS	ER COORDINATOR DORDINATOR DORDINATOR DORDINATOR DESCRIPTION BIOFILTRATION-BIO BIOFILTRATION-BIO GSRD - CONDRETE I CONT. DEFLECTION DETENTION BASIN	STRIP SVALE SVALE SEPARATION					3Y	
STORHWATE ASST. SW C4 C0HHEUTS: IHHSTradealDa IHHSTradealDa BIOSTP BIOSTP BIOSTP BIOSTP BIOSWL CNTEOX CNTEEF DETBAS DRINLT	ER COORDINATOR DORDINATOR DORDINATOR DESCRIPTION BIOFILTRATION-BIO BIOFILTRATION-BIO BIOFILTRATION-BIO GSRD - CONDRETE I CONT. DEFLECTION DETENTION BASIN DETENTION BASIN	STRIP -SWALE BOX INCLINED SC SEPARATION					3Y	
STORHWATE ASST. SW C4 C+HHE#T5: HHIS Trolarator IMMS CODE BIOSTP BIOSWL CNTBOX CNTDEEF DETBAS DRINLT INDBAS	ER COORDINATOR DORDINATOR DORDINATOR DORDINATOR DORDINATOR BIOFILTRATION-BIO BIOFILTRATION-BIO GIORILTRATION-BIO GIORILTRATION-BIO DEFLECTION DEFLECTION DEFLECTION DEALN INLET INSERT INFLITRATION DEVIS	STRIP -STRIP -SWALE BOX INCLINED SC SEPARATION -SE - BASIN					3¥	
STORHWATE ASST. SW CO CONNECTS: IMMS CODE BIOSTP BI	ER COORDINATOR DORDINATOR DORDINATOR DORDINATOR DORDINATOR DESCRIPTION BIOFILTRATION-BIO BIOFILTRATION-BIO BIOFILTRATION DEVIS INFLITRATION DEVIS INFLITRATION DEVIS	STRIP SWALE BOX INCLINED SC SEPARATION SE - BASIN SE - TRENCH					ξΥ 	
STORHWATE ASST. SW C4 C4HHEUTS: IMMS CODE BIOSTP BIOSTP BIOSWL CNTBOX CNTDEEF DETBAS DRINLT INDBAS INDTRE LINGTBE	DORDINATOR DORDINATOR DORDINATOR DOSCRIPTION BIOFILTRATION-BIO BIOFILTRATION-BIO GSRD - CONDRETE I CONT. DEFLECTION DETENTION BASIN DETENTION BASIN DRAIN INLET INSERT INFLITRATION DEVIS INFLITRATION DEVIS GSRD - (LONG TUBE	-STRIP -STRIP -SWALE BOX INCLINED SC SEPARATION 	REEN				3Y	
STORHWATE ASST. SW C4 C+HHE#T5: HHH5 Tradevaller IMH5 CODE BIOSTP BIOSTP BIOSTP BIOSWL CNTBOX CNTDEFF DETBAS DARINLT INDBAS INDTRE LNGTBE MCTT	ER COORDINATOR DORDINATOR DORDINATOR DORDINATOR DESCRIPTION BIOFILTRATION-BIO BIOFILTRATION-BIO BIOFILTRATION-BIO GSRD - CONDRETE I CONT. DEFLECTION DETENTION BASIN DETENTION BASIN INFLITRATION DEVIS INFLITRATION DEVIS INFLITRATION DEVIS INFLITRATION DEVIS BAIN INLET INSER MULTI CHAMBERED	STRIP SWALE BOX INCLINED SC SEPARATION SE - BASIN SE - BASIN SE - TRENCH JLINEAR RADIAL JTREATMENT TR	REEN				3Y	
STORHWATE ASST. SW C CONNERTS: IMMS CODE BIOSTP BIOSWL CNTBOX CNTDEFF DETBAS DERINLT INDEAS INDTRE LNGTBE MCTT MF-ADS	ER COORDINATOR DORDINATOR DORDINATOR DORDINATOR DORDINATOR DESCRIPTION BIOFILTRATION-BIO BIOFILTRATION-BIO BIOFILTRATION-DEVIS DRAIN INLET INSERT INFLITRATION DEVIS INFLITRATION DEVIS SINFLITRATION DEVIS DRAIN INLET INSERT INFLITRATION DEVIS DRAIN INLET INSERT INFLITRATION DEVIS DRAIN INLET INSERT INFLITRATION DEVIS GSRD - (LONG TUBE MULTI CHAMBERED MULTI CHAMBERED	STRIP -SWALE BOX INCLINED SC SEPARATION F SE - BASIN SE - TRENCH) LINEAR RADIAL) LINEAR RADIAL TREATMENT TR 'IN/DELAWARE S.	REEN				3Y	
STORHWATE ASST. SW CO CONHESTS: IMMS CODE BIOSTP BI	ER COORDINATOR DORDINATOR DORDINATOR DORDINATOR DESCRIPTION BIOFILTRATION-BIO BIOFILTRATION-BIO BIOFILTRATION-BIO DETENTION BASIN DRAIN INLET INSERT INFLITRATION DEVIS INFLITRATION DEVIS INFLITRATION DEVIS INFLITRATION DEVIS INFLITRATION DEVIS MEDIA FILTER-AUST MEDIA FILTER-COM	STRIP SWALE BOX INCLINED SC SEPARATION F SE - BASIN SE - TRENCH) LINEAR RADIAL ITREATMENT RADIAL ITREATMENT RADIAL DINEAR RADIAL SE - TRENCH) ST FILTERS	REEN				3Y	
STORHWATE ASST. SW C4 C+HHEUTS: C+HHEUTS: IHHS Tredenal De INTES CODE BIOSTP BIOSTP BIOSTP BIOSTP BIOSTP BIOSTP BIOSTP BIOSTP BIOSTP BIOSTP CHTEOX CH	CORDINATOR DORDINATOR DORDINATOR DORDINATOR DORDINATOR DESCRIPTION BIOFILTRATION-BIO BIOFILTRATION-BIO GSRD - CONDRETE I CONT. DEFLECTION DETENTION BASIN DETENTION BASIN DETENTION BASIN DETENTION DEVIS INFLITRATION DEVIS INFLITRATI	STRIP SWALE BOX INCLINED SC SEPARATION F SE - BASIN SE - TRENCH) LINEAR RADIAL ITREATMENT RADIAL ITREATMENT RADIAL DINEAR RADIAL SE - TRENCH) ST FILTERS	REEN				3Y	
STORHWATE ASST. SW C4 C4HHEWTS: C4HHEWTS: IHHS Treatently IHHS CODE BIOSVL CNTBOX CNTDEFF BIOSVL CNTDEFF DETBAS DAINLT INDBAS INDTRE LNGTB MF-ADS MF-CMP OILWTR ST-FLT	ER COORDINATOR DORDINATOR DORDINATOR DORDINATOR DESCRIPTION BIOFILTRATION-BIO BIOFILTRATION-BIO BIOFILTRATION-BIO GSRD - CONDRETE I CONT. DEFLECTION DETENTION BASIN DETENTION BASIN INFLITRATION DEVIS GSRD - CONDRETE I CONT. DEFLECTION DETENTION BASIN DETENTION BASIN DETENTION BASIN DETENTION BASIN DETENTION DEVIS GSRD - CONDRETE I MULTI CHAMBERED MEDIA FILTER-AUST MEDIA FILTER-COM OLL/WATER SEPERA STORM FILTER	DATE SENT DATE SENT STRIP SWALE BOX INCLINED SC SEPARATION SE - BASIN SE - BASIN SE - BASIN SE - BASIN SE - TRENCH J LINEAR RADIAL TREATMENT TR TIN/DELAWARE S. POST FILTERS TOR	REEN				3Y	
STORHWATE ASST. SW C4 C+HHEUTS: C+HHEUTS: IHHS Tredenal De INTES CODE BIOSTP BIOSTP BIOSTP BIOSTP BIOSTP BIOSTP BIOSTP BIOSTP BIOSTP BIOSTP CHTEOX CH	CORDINATOR DORDINATOR DORDINATOR DORDINATOR DORDINATOR DESCRIPTION BIOFILTRATION-BIO BIOFILTRATION-BIO GSRD - CONDRETE I CONT. DEFLECTION DETENTION BASIN DETENTION BASIN DETENTION BASIN DETENTION DEVIS INFLITRATION DEVIS INFLITRATI	STRIP -SWALE BOX INCLINED SC SEPARATION F SE - BASIN SE - TRENCH) LINEAR RADIAL SE - TRENCH) LINEAR RADIAL TREATMENT TR TIN/DELAWARE S. POST FILTERS TOR FER VAULT	REEN				3Y	
STORHWATE ASST. SW CI CONTRETS: IMMS CODE BIOSTP BIOSWL CNITBOX CNITBOX CNITBOX CNITBOX CNITBOSTP BIOSWL CNITBOX CNITBOSTP BIOSWL CNITBOX CNITBOSTP BIOSWL CNITBOSTP BIOSWL CNITBOSTP BIOSWL CNITBOSTP BIOSWL CNITBOSTP BIO	ER COORDINATOR DORDINATOR DORDINATOR DORDINATOR DORDINATOR DESCRIPTION BIOFILTRATION-BIO BIOFILTRATION-BIO BIOFILTRATION-BIO GSRD - CONDRETE I CONT, DEFLECTION DETENTION BASIN DRAIN INLET INSERT INFLITRATION DEVIS INFLITRATION DEVIS INFLITRATION DEVIS GSRD - (LONG TUBE MUDIA FILTER-COM MEDIA FILTER-COM OL/WATER SEPERA STORM FILTER TR2000 FABRIC FILT TRACTION SAND TR	STRIP -SWALE BOX INCLINED SC SEPARATION F SE - BASIN SE - TRENCH) LINEAR RADIAL SE - TRENCH) LINEAR RADIAL TREATMENT TR TIN/DELAWARE S. POST FILTERS TOR FER VAULT	REEN				3Y	
STORHWATE ASST. SW C4 C+HHEWTS: C+HHEWTS: IMMS CODE BIOSTP BIOSTP BIOSTP BIOSTP BIOSTV CHTBOX CHTBOX CHTBOX CHTBOX CHTBOX DRINLT INDBAS INDTRE LNGTBE MGTT MF-CMP OILWTR ST-FLT TR2FFV TRCSND	ER COORDINATOR DORDINATOR DORDINATOR DORDINATOR DORDINATOR DESCRIPTION BIOFILTRATION-BIO BIOFILTRATION-BIO BIOFILTRATION-BIO CONT. DEFLECTION DETENTION BEVIS INFLITRATION DEVIS INFLITRATION DEVIS INFLITRATION DEVIS INFLITRATION DEVIS INFLITRATION DEVIS GSRD - (LONG TUBE MULTI CHAMBERED MULTI C	STRIP -SWALE BOX INCLINED SC SEPARATION F SE - BASIN SE - TRENCH) LINEAR RADIAL SE - TRENCH) LINEAR RADIAL TREATMENT TR TIN/DELAWARE S. POST FILTERS TOR FER VAULT	REEN				3Y	



Enter TBMPs into Database





Questions?



The Flow of Stormwater on Vtrans Projects An Evolving Process



Jennifer Callahan

Stormwater Technician

Vermont Department of Transportation



Heather Voisin


Green Infrastructure Engineer

Vermont Department of Transportation



The Flow of Stormwater on VTrans Projects An Evolving Process

Jennifer Callahan & Heather Voisin





...to maintenance





Regulations

ACT 64 – VERMONT'S CLEAN WATER ACT

• A BROAD SUITE OF PROGRAMS AND REGULATIONS TO ADDRESS WATER QUALITY INCLUDING:

- TRANSPORTATION SEPARATE STORM SEWER
 GENERAL PERMIT (TS4)
 - MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4)
 - MULTI-SECTOR INDUSTRIAL GENERAL PERMIT (MSGP)
 - STATE OPERATIONAL STORMWATER
 DISCHARGES (STATE OSW)
 - TOTAL MAXIMUM DAILY LOAD(TMDL)

CONSTRUCTION STORMWATER DISCHARGES (NOT PART OF TS4)

STATE OPERATIONAL PERMIT

STATEWIDE PROGRAM REQUIRED ON PROJECTS THAT CREATE AN ACRE OR MORE OF IMPERVIOUS SURFACE.

Regulations

- THIS THRESHOLD WILL BE LOWERED TO 1/2 ACRE IN 2021.
- AVERAGE FOR VTRANS IS 10 PROJECTS PER YEAR OBTAIN UNDER THIS PROGRAM
 - EXPECTING THAT TO AT LEAST DOUBLE WITH THE THRESHOLD LOWERING
- CURRENTLY 86 PROJECTS CONSTRUCTED AND BEING MAINTAINED (AND GROWING).
- ANOTHER 54 PROJECTS UNDER DESIGN DEVELOPMENT, PERMITTING OR CONSTRUCTION.

TMDL IMPLEMENTATION

- REQUIRES THE CONSTRUCTION OF STORMWATER TREATMENT ON NEW AND EXISTING
 IMPERVIOUS SURFACES.
- IDENTIFY AND IMPLEMENT SW RETROFITS TO ADDRESS TMDLS/WQRPS
 - LAKE CHAMPLAIN PHOSPHORUS
 - STORMWATER IMPAIRED WATERSHEDS
 - OTHERS....
- ABOUT 60 PRACTICES PLANNED FOR SW-IMPAIRED WATERSHEDS, EXPECTING MANY MORE FOR LCTMDL
 - CURRENTLY HAVE 17 CONSTRUCTED, 20 DESIGNED AND PLANNED FOR CONSTRUCTION NEXT SEASON






CONSTRUCTION GENERAL PERMIT

- STATEWIDE PROGRAM REQUIRED ON PROJECTS THAT HAVE AN ACRE OR MORE OF EARTH DISTURBANCE.
- TIERED PROGRAM BASED ON ASSESSMENT "RISK"
 - LOW RISK GENERAL PERMIT
 - MODERATE RISK GENERAL PERMIT
 - INDIVIDUAL PERMIT
- ON AVERAGE 30 VTRANS PROJECTS PER YEAR NEED THIS PERMIT










Online Shared Reviews Preliminary Plans – Constructability Meeting Final Plans – PS & E Pre-contract Meeting



November 14, 2018 Special Provisions for: Williston STE 1M SWFR(1) Under Vermont Construction General Permit 3-9020

Construction signs shall be installed so as to nor obstruct the view of existing traffic contro sight distance, and corner sight distance f highways. (e) (£)

Speed zones, if used, should be a maximum of Posted speeds. Temporary speed limit cortif by the Chief Engineer.

OFICE TO BIDDERS. All retroreflective sheeting NOTICE TO BIDDERS. All retroreflective sheeting to remain after the project in completed) sha 4956 Type III sheeting, unless otherwise show

<u>BOTICE TO BIDDERS - CONTREPORT CONSTRUCTION</u>, of the following Virans construction projec to the west of this project during its cont 20.

TBD project TBD IM SURF(63) Williston STP FPAV(10) TBD Waterbury-Richmond The Contractor shall coordinate control with the work required for

There will be no extra compens inconvenience caused by working

ENVIRONMENTAL. (a) Threatened, Endangered, a (1) This project shall 21.

This project shall Measures to protect long-eared bat. W Time-of-Year (70Y autable bat hab)
 A madiar habi

- 2 3" and/or habi
- is anticipa
- It is anticip trees 23" in part of the in a finding
- in a ringing bridge rela without any
- (3) The Contr
- restricti Cutting
- limits waste,

EVELOPTION COLOR ALLOS A LOSS Date of Authorization: Date of Expiration: November 13, 2018 Date or Expiration: November 12, 2023 The project listed above has received authorization under General Permit 3-9020 to discharge stormwater from the following construction activities:

Notice of Authorization

For Moderate Risk Projects

tomstruture extraines: installation of new operational stormwater BMPs along the interstate mediae with associated access roads and drainage infrastructure and a restorift of the existing wet nond at the northbound rest area with associated access road and drainage infrastructure. installation of new operational stormwater MMPs along the interstate median with associated access roads and drainage infra and a retrofit of the existing wet pond at the northbound rest area with associated access road and drainage infrastructure.

 Implementation increases the todowing requirements:
 Implementation of the authorized site-specific Erosion Prevention and Sediment Control Plan as prepared by: *i* and and *i* and Sbeet 5 of 54, "Typical Sections and Details Sheet 1", dated 10/2/2018; Sheet 6 of 54, "Typical Sections and Details Sheet 2", dated 10/2/2018; Sheet 9 of 54, "Quantity Sheet (1 of 2)", dated 10/2/2018; Sheet 8 of 54, "Quantity Sheet (2 of 2)", dated 10/2/2018; Sheet 9 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 10 of 54, "Layout Plan Sheet (2 of 10)", dated 10/2/2018; Sheet 11 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, Sheet Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet (3 of 10)", dated 10, 20 2)", dated 10/2/2018; Sheet 9 of 54, "Layout Plan Sheet (1 of 10)", dated 10/2/2018; Sheet 10 of 54, "Layout Plan Sheet (2 of 10)", dated 10/2/2018; Sheet 11 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan Sheet Sheet (4 of 10)", dated 10/2/2018; Sheet 13 of 54, "Layout Plan Sheet (3 of 10)", dated 10/2/2018; Sheet 12 of 54, "Layout Plan "Layout Plan Sheet (6 of 10)", dated 10/2/2018; Sheet 13 of 54, "Layout Plan Sheet (6 of 10)", dated 10/2/2018; Sheet 14 of 54, "Layout Plan Sheet (6 of 10)", dated 10/2/2018; Sheet 17 of 54, "Layout Plan Sheet (7 of 10)", dated 10/2/2018; Sheet 16 Sheet 18 of 54, "Layout Plan Sheet (10 of 10)", dated 10/2/2018; Sheet 19 of 54, "EPSC Narrative (1 of 2)", dated 10/2/2018; of 54, "Layout Plan Sheet (8 of 10)", dated 10/2/2018; Sheet 17 of 54, "Layout Plan Sheet (9 of 10)", dated 10/2/2018; Sheet 19 of 54, "Layout Plan Sheet (10 of 10)", dated 10/2/2018; Sheet 19 of 54, "EPSC Narrative [1 of 20]", dated 10/2/2018; 10/2/2018; Sheet 20 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 21 of 54, "EPSC Characterized Sheet (2 of 3)", dated 10/2/2018; Sheet 22 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 23 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 23 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 23 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 33 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 33 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 33 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 33 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 33 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 33 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 33 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 33 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 33 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 33 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 33 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 33 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 33 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 33 of 54, "EPSC Detail Sheet (3 of 54, "EPSC Detail Sheet

10/22018; Sheet 20 of 54, "EPSC Narrative (2 of 2)", dated 10/2/2018; Sheet 21 of 54, "EPSC Detail Sheet (1 of 3)", dated 10/2/2018; Sheet 22 of 54, "EPSC Detail Sheet (2 of 3)", dated 10/2/2018; Sheet 23 of 54, "EPSC Detail Sheet (1 of 3)", of 3", dated 10/2/2018; and all summirine information. a) of source reaction for any any provide international and any provide international and internatindependent and international and international and internation All areas of disturbance must have temporary or final stabilization within 7 days of the initial disturbance. After this time, all disturbed soil must be stabilized at the end of each work day. Between October 15 and April 15 all disturbed soil must be addition of the end of each work day. The 6 dlouising exversions analy:

- Stabilization is not required if work is to continue in the area within the next 24 hours and there is no maximization forward for fun next 24 hours. Stabilization is not required if the work is occurring in a self-contained excavation (i.e. no outlet) with a depth of 2 due to present for a bound Constant secondarian excavation will be taken bound.
- The total authorized disturbance is 4.57 acre(s).
- oncontranton to non-required it time works in securiting the a neurospination 2 feet or grouter (e.g. house foundation excavation, utility trenches).
- No more than 2 acres of land may be disturbed at any one time.

- Inspections shall be conducted at least once every (7) calendar days and within twenty-four (24) hours of the end of a chirm event resultion in discharge of dominanter from construction size.
- accurate transmission transmission to the second state of the second stat
- If there is a discharge of visibly discolored stormwater from the construction site or from the construction site to waters of the State, the permittee shall take immediate corrective action. If, after completing corrective action, there continues to be a discharge of sediment from the construction site to waters of the State, the permittee shall notify DEC by submitting a report within 72 hours of the discharge.
- report writin 1/2 nours of the disconrige.
 The On-site Plan Coordinator shall have a copy of the approved [EPSC Plan and all amendments available at a central focation on-site for the use of all those identified as having responsibilities under this authorization whenever they are on the construction site. If an on-site location is unavailable to store the EPSC Plan when no personnel are present, notice of the construction site. If an on-site location is unavailable to store the EPSC Plan when no personnel are present, notice of the construction site. location on-site for the use of all those identified as having responsibilities under this authorization whenever they are on the construction site. If an on-site location is manyaleble to store the EPSC Plan when no personnel are present, hotice of the EPSC starte trouble to be averaged near the wasin antraneous at the construction eits. the construction site. If an on-site location is maxvalable to store the 13/SC Vian when the EPSC plan's location shall be posted near the mails entrance at the construction site. ¹⁰ request informations on the documentation of the provided planet of the stores blance in the store blance in the store blance in the stores blance in the store blance in
- Construction General Permit dated 11.13.18 DEC, Watershot Manageme Main Ballaing, Second Flor One National Life Drive Mantpelier, VT 05620

Contract Review for Environmental **Commitments & Permit Conditions**

Kick-off Meeting & Preconstruction Conference

141

- VERMONT

Conduct Pre-construction Meeting for Projects with Individual Construction Stormwater Permits







FIELD VISITS

0














Conduct Pre-final Site Visit



Final Inspection






Follow Up Visits, As Needed








Maintenance

- \bigcirc
- CONSULTATION DURING THE DESIGN PROCESS
- PRE-FINAL MEETING WITH CONSTRUCTION
- ♦ CREATE MAINTENANCE PLAN
- MEET WITH DISTRICT STAFF
- ANNUAL INSPECTIONS
- RENEWALS EVERY 5 YEARS
- MAINTENANCE AS NEEDED


• TIME OF YEAR



• TIME OF YEAR



• TIME OF YEAR



DIFFERING SITE
 CONDITIONS



• "TOO LATE TO FIX IT"



- Enhanced Communication And Coordination Between Highway Division Stormwater Staff
 - Regular Check-Ins on Projects



- Enhanced Communication And Coordination Between Highway Division Stormwater Staff
 - Regular Check-Ins on Projects
 - Conducting Pre-final Inspection



- Enhanced Communication And Coordination Between Highway Division Stormwater Staff
 - Regular Check-Ins on Projects
 - Conducting Pre-final Inspection
 - Monthly Meetings For All Highway Division Stormwater Staff



- Enhanced Communication And Coordination Between Highway Division Stormwater Staff
 - Regular Check-Ins on Projects
 - Conducting Pre-final Inspection
 - Monthly Meetings For All Highway Division Stormwater Staff
 - Participating In Shared Reviews During Design



QUESTIONS???

CoP Questions/Discussion



Pete Riegelhuth

Heather Voisin

Transportation

Vermont Department of

Heather.Voisin@vermont.gov

California Department of Transportation

pete.riegelhuth@dot.ca.gov



Melissa Savage AASHTO CEE msavage@aashto.org



Jennifer Callahan

Vermont Department of Transportation Jennifer.Callahan@vermont.gov



Scott McGowen

Michael Backer International Scott.McGowen@mbakerintl.com




Closing

A recording of this webinar will be available on the Center for Environmental Excellence by AASHTO Website.

http://environment.transporation.org

Products & Programs → Communities of Practice → Stormwater Management









Thank You for Attending

